Scott. M-27—20,000—19-11-42

Development (1944) Department

MS SERIES.

Passed

G.O. No. 2133

Dated 18-5-44

[Despatch Abstract.]

Industries — Sericulture — Kollegal Silk Filatures, Kollegal — Managers quarters — Construction of Lavatory — Expenditure — Sanctioned

C.F. 32 (a).

Enclosures never sent only to SW

Pc. AT 3718/6.5.116 for enclosures to send

From (Name) A. [illegible], Esq., I.C.S.,

Department

Designation Director of Industries and Commerce,

Station Guindy, Madras

Received ..... Registered D/44

To

The Secretary to Government,
Development Department.

SECRETARIAT UNDER GOVERNMENT
4 - MAY 1944
DEVELOPMENT DEPARTMENT

Enclosures:

No. 936-D/44 dated 29th April 1944 194

Sir,

Sub:- Industries - Kollegal Silk Filatures, Kollegal - Managers quarters - Lavatory - Construction of - Sanction - Requesting.

It is found necessary to construct a lavatory for the Manager's quarters, Kollegal Silk Filatures, Kollegal, as there is none at present attached to the quarters. I have had the necessary estimate prepared by the Industrial Engineer for the construction of a lavatory. I enclose the plan and estimate in respect of the above work for the information of Government and request that Government may be pleased to accord sanction to the incurring of an expenditure not exceeding Rs.360/- (Rupees three hundred and sixty only) for the purpose.

2. As the work was urgent, I instructed the Special Supervisor to take it up in anticipation of Government sanction. I request that my action may be approved.

pp 3-11 below

Ans pp 9 below

M

3 The expenditure is debitable to "85-A. Capital outlay on Provincial Schemes connected with War 1939 C. other Miscellaneous schemes - G. Kollegal Silk Filatures, Kollegal - 6, Buildings, Plant and Machinery and other equipment".

for Director of Industries & Commerce.

Copy to the Industrial Engineer, Madras.
Copy to the Manager, Kollegal Silk Filatures, Kollegal.

IVS/3-5.

Name of work:- Constructing a lavatory for Manager's Quarters - Kollegal Silk, Filatures, Kollegal.

No.	Particulars of work.	No.	Measurement in feet. Length.	Breadth.	Depth.	Total.	Total.
1.	Earthwork excavation for Foundations.						
	Main walls all round.	1	28'-6"	2'-6"	3'-0"	214	
	Below seat in front.	1	4'-7½"	1'-6"	1'-0"	7	
	Sides.	2	2'-0¾"	1'-6"	1'-0"	6	
	Steps.	1	2'-3¾"	2'-6"	0'-6"	3	
						230	230
2.	Concrete broken stone Lime Mortar 1 : 8.						
	Main walls all round.	1	28'-6"	2'-6"	1'-0"	71	
	Below seat front wall.	1	4'-7½"	1'-6"	1'-0"	7	
	" Sides.	2	2'-0¾"	1'-6"	1'-0"	6	
	Steps.	1	2'-3¾"	2'-6"	0'-6"	3	
	Total.					87 or	90
3.	Brick work in lime mortar 1 : 2.						
	Foundations - 1st footing.						
	Main walls.	1	28'-6"	1'-10½"	1'-0"	53	
	" 2nd footing.	1	28'-6"	1'-6"	1'-0"	43	
	Basement.	1	28'-6"	1'-1½"	1'-6"	48	
	Below seat front wall.	1	6'-0"	0'-9"	2'-0"	9	
	" sides.	2	3'-1½"	0'-9"	2'-0"	9	
	Steps.	1	2'-6"	2'-0"	0'-6"	3	
	"	1	2'-6"	1'-0"	0'-6"	1	
	Sides of door.	2	6'-0"	1'-1½"	1'-0"	14	*
	Allx round ventilator.	1	10'-0"	1'-1½"	1'-0"	11	*
	Below wall plate.	2	8'-3"	1'-1½"	1'-0"	19	*
	Top of gubles.	2	6'-2"	1'-1½"	1'-0"	14	*
	Total					224	
	Deduction.						
	Rear opening.	1	1'-3"	1'-1½"	1'-2"	2	
	Lintal over rear opening.	1	2'-6"	1'-1½"	0'-4"	1	
	Lintal over ventilator.	1	3'-6"	1'-0"	0'-3"	1	
	Total					4	
	Net total less deductions (224 - 4)					= 220	220
4.	Brick work in clay, with country bricks.						
	Superstructure - Main walls.	1	28'-6"	1'-1½"	6'-9"	211	
	Sides triangular portion.	2	8'-3"	1'-1½"	4'-0"	37	
	Portion front.	1	6'-0"	1'-1½"	3'-2"-9"	25	
	Total.					273	
	Deduction.						
	Door.	1	2'-6"	1'-1½"	6'-0"	17	
	Ventilator.	1	2'-0"	1'-1½"	1'-0"	2	
	Door lintal.	1	4'-0"	1'-1½"	0'-4"	2	
	Lime mortar in item (3) (*)					58	
	Total.					79	
	Net total less deductions (273 - 79)					=194 or	200
5.	Cut stone two lines dressed fixed in cement mortar 1 : 3.						
	Lintal over door.	1	4'-0"	2'-1½"	0'-4"	.5	
	" under opening rear.	1	2'-3"	1'-3½"	0'-4"	0.84	
	Total.					2.34	or 2.5

P.T.O.

(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
6.	Country wood brought and put up:-						
	Wall plate.	2	8'-3"	0'-3"	0'-2"	0.69	
	Rafter.	3	10'-9"	0'-2"	0'-3"	1.34	
	End rafters.	2	4'-0"	0'-2"	0'-3"	0.33	
	Ventilator plankx.	1	3'-6"	1'-0"	0'-3"	0.88	
						3.24	or 3.3
	Roofing with Mangalore Tiles.						
	Over C.W. Reefers 2" X 1"	1	7'-1½"	10'-9"		73	
	at end.	1	2'-0"	0-6¾"		2	
						75	75
8.	Plastering with cement mortar 1 : 3. ½" thick.						
	Inside walls all round, for 2'	1	24'		2'	48	
	Top of steps.	1	2'-6"	2'		5	
	Sides.	2	1'-0"		1'-0"	2	
	"	2	1'-0"		0'-6"	1	
	Face.	1	2'-6"		1'-6"	4	
	Below seat inside all round.	1	10'-9"		1'-6"	16	
	Side of opening.	1	4'-10"	1'-1½"		6	
						82	
	Deduct opening of door.	1	2'-6"		2'-0"	5	
	Net Total.					77	or 80
	Plastering with lime mortar 1 coat ½" thick and white washing two coats.						
	Inside front wall.	1	6'-0"	10'-6"		63	
	" rear.	1	6'-0"	7'-0"		42	
	" sides.	2	6'-0"	$\frac{10'-6"+7'}{2}$		105	
	Outside Basement.	1	33'	1'-6"		50	
	Front wall.	1	8'-3"	10'-9"		89	
	Rear wall.	1	8'-3"	6'-6"		54	
	Side walls.	2	8'-3"	$\frac{10'-9"+6'-6"}{2}$		142	
	Top and sides of door.	1	14'-6"	0'-9½"		12	
	Sides and bottom of Ventilator.	1	4'-0"	0'-10½"		4	
						561	
	Deductions.						
	Door.	2	2'-6"	6'-0"		30	
	Ventilator.	2	2'-0"	1'-0"		4	
	Steps.	1	2'-6"	1'-6"		4	
	Ventilator lintals.	2	3'-6"	0'-3"		2	
	Rear opening.	1	1'-3"	1'-2"		2	
	Cement plastering inside.	1	24'-0"	2'		48	
						90	
	Net total less deductions.					471	or 480
	Flooring with 4" lime concrete and plastered over with cement mortar 1 : 3. ½" thick.						
	Inside room.	1	6'-0"	6'-0"		36	
	Below seat.	1	2'-6¾"	2'-6¾"		6	
						42	
	Deduct seat.	1	3'-10½"	3'-9"		15	
	Portion of wall.	1	2'-3"	0'-9"		2	
						17	
	Net total less deduction.					25	or 30

P.T.O.

11.	Country wood doors. 2'-6" X 6'-0" framed and planked complete.			1	
12.	Country Wood ventilator 2' X 1' planked complete.			1	
13.	Providing R.C. squatting plate 2" thick 3' X 3'-6"			1	
14.	Providing country wood plank flap shutter with hooks, hinges etc. complete including tarring.			1	
15	Providing country wood pans 15" X 10" X 6" including tarring.			1	
16.	Painting with grey paint 2 coats.				
	Doors.	1 X 2½	2'-6" 6'-0"	34	
	Ventilator.	1 X 2½	2'-0" 1'-0"	5	
	Wooden lintal.	1	2'-0" 1'-6"	3	
	Rafters.	3	8'-8" 0'-8"	17	
		2	2'-0" 0'-8"	3	
				--	
	Total.			62	or 70
17.	Providing leading drain.			L.S.	
18.	Contingencies and petty supervision.			L.S.	

ABSTRACT

Quantity.	Particulars of work.	Rate. Rs. As. Ps.	Per.	Amount. Rs. As. Ps.	Total.
230 c.ft.	(1) Earthwork excavating foundation.	7- 8- 0	1000 c.ft.	2- 0- 0	
90 "	(2) Concrete broken stone in lime mortar.	36-0- 0	100 c.ft.	32- 0- 0	
220 "	(3) Brick work in lime mortar 1 : 2	38- 0- 0	"	84- 0- 0	
200 "	(4) Brick work in clay with country bricks.	27- 0- 0	"	54- 0- 0	
2.5 "	(5) Cut stone 2 lines dressed in C.M. 1:3	2- 4- 0	1 cft.	6- 0- 0	
3.3 "	(6) Country wood wrought and put up.	8- 0- 0	"	26- 0- 0	
75 sq. ft.	(7) Roofing with Mangalore Tiles.	46- 3- 0	100 sq.ft.	35- 0- 0	
80 "	(8) Plastering with cement mortar 1:3	7- 1- 0	"	6- 0- 0	5% increase.
480 "	(9) Plastering with lime mortar 1 coat and white washing two coats.	6- 0- 0	"	29- 0- 0	
30 "	(10) Flooring with 4" lime concrete and plastered under with cement mortar ½" thick 1:3	20- 0- 0	"	6- 0- 0	
1 No.	(11) Country wood door 2'-6" X 6" framed and planked complete.	30-12-0	each.	31-0- 0	proportionate rate for door.
1 No.	(12) Country wood ventilator 2' X 1" planked.	5-12-0	"	6- 0- 0	5% increase over enhanced rate.
1No.	(13) Providing R.C. squatting slab 2" thick 3' X 3'-6"	8- 5- 0	"	8- 0- 0	5% increase.
1 No.	(14) Providing country wood plank flap shutter.	5- 8- 0	"	6- 0- 0	"
1 No.	(15) Providing country wood pan 15" X 10" X 6"	4-12- 0	"	5- 0- 0	"
70 Sq.ft.	(16) Painting with grey paint 2 coats.	4- 8- 0	100 sq. ft.	3- 0- 0	
			C/F Rs.	389- 0- 0	

P.T.O.

	B/F.		Rs.	3[illegible]
L.S	(17) Providing leading masonry drain.	L.S.	"	6
	(18) Contingencies and petty supervision.		"	15
		Total.	Rs.	360

1A

Dev. Dept

Issue Docket Pl. Sub Industries – Sericulture – Kollegal Silk Filatures, Kollegal – Managers quarters – Construction of Lavatory – ~~Construction~~ – Expenditure – Sanctioned

Rs 18.5.44 69/1915

26153 D/44 13/1915 Ref-1 From the D. I & C, no. 936 D/44 d 29.4.44

Order no. 2133 (HS) Dev. d 18.5.44

~~The plan and estimate submitted by the D. I & C for the Construction of a Lavatory for the Managers quarters, Kollegal Silk Filatures, Kollegal are approved.~~ The D. I & C. is permitted to incur an expenditure not exceeding Rs 360/- (Rupees three hundred and Sixty only) ~~as detailed in the estimate~~ for the ~~work~~ Construction of a Lavatory for the Managers' Quarters, Kollegal Silk Filatures, Kollegal.

para 1, p 1 cf- The ~~suspension~~ action of the D. I & C. in ~~having~~ taking up the work in anticipation of the sanction of the Govt. is approved

Min p 1 cf

C.6153/41

2. The expenditure should be debited to "85A-Capital outlay on Provincial Schemes Connected with the War 1939- Other Miscellaneous Schemes- (i) Kollegal Silk Filatures Kollegal- 6 Buildings, Plant & Machinery and other equipment

2 cl

11.5.44

Approved

210:139

To The D. Dy C.

" A.G. through Finance

Copy to S.F.

Note Please see the letter from the D. Dy C. at pp 1-2 of Subject to orders, a draft order is submitted for approval. It may be sent to the Dept. for acceptance.

Draft 2403-3/44-2

11.5.44

162 D/Secy

3

44

Fin (Exp B)

The draft order may be accepted

Rev No. 2104 (Fin)
13.5.44

KAN
13.5.44 Dev

12/5/44 28162 D/44

Dev Dept

To U.S.

for orders whether the draft ords/~~slow~~ at pp 1-2 above may issue now

13.5.44 Dev 14.5.44

Nay verus. 15.5.44 Secy to Govt

Sent to AS II by Fin (Exp B) by messenger

[Issued as G.O. no. 2133 (HS) Dev d 18.5.44]

13-5-44

Clear